

National Institute of Public Finance and policy

FINANCIAL BID

Renovation of Auditorium

S.No	DESCRIPTION	QTY.	RATE(Inclusive of all taxes and cartage)	AMOUNT(Inclusive of all taxes and cartage)
1.	Demolishing existing damaged paneling on walls by way removing kota stone strips, wooden bands etc. complete	3200 sft		
2.	Disposal of debris from site from time to time by mechanical transport including loading /unloading	LS		
3.	P/F of Teak wood bands matching with existing wooden bands in paneling complete with moulding as per approved Design (C P Teak / Burma Teak / Steem Beach kiln seasoned and chemically treated for termite)	1680 rft		
4.	P/Fixing of kota stone strips matching with existing on wall paneling a) New stone b) Fixing of existing stone strips available	960 sft 2240 sft		
5.	Appling two or more coats of plastic emulsion paint on old surface of approved shade on ceilings including thoroughly cleaning the surface, sand papering etc. (Asian, Berger, Nerolac) (HT. above 20')	1600 sft		
6.	Texture paint on walls (old surface) two or more coats of approved shade including cleaning the surface / sand papering complete	1700 sft		
7.	P/F of Reception Desk with Granite Top made up of 18mm thick commercial board(termite resistant and water proof) with teak veneers & finished with melamine polish as per approved Drawing and design (size 10'x3'and 2' wide)	One unit		
8.	Providing melamine polish on wooden surface a) New Teak wood bands (9"wide)	1680 rft		
	b) Existing fixed / move able furniture (Tables) by way of removing existing polish including repairs as required	LS		
9.	P/F of Teak veneer of approved shade on existing Doors including cost of SS Handles 18", Locks, Hinges etc. complete with melamine polish (Basic cost of veneer 60/sft)	400 sft		
10.	P/F of new carpet complete with wastage & cartage including above for removing the existing carpet and stacking the same at designated site inside the premises (unitex or equivalent of approved shade and quality)	1800 sft		

11.	Electrical works			
a	P/Fixing tube light (rod) 2' length warm day light in existing fixture fitted in ceiling (Phillips/Crompton or equivalent)	112 No.		
b	Repairs to existing light fixtures by way of replacing damaged chowk / starter etc. & P/Fixing modular switches sockets etc. including wiring in conduit / Chanel wherever exposed behind reception desk. (modular switches North west/Anchor Roma)	LS		
12.	Repairs to existing chairs including rubberized and other material by way of replacing the upholstery of approved shade and quality (min cost 450/- per mt.). The sample of the material will be approved by the Institute	85 No.		
13.	Providing Anti termite treatment to all wooden members and complete floor area inside auditorium (Standard ISI make)	2500 sft		
	GRAND TOTAL INCLUSIVE OF ALL TAXES AND CARTAGE			

DATED

SIGNATURE

NAME AND ADDRESS OF THE FIRM

MOBILE NO

SEAL OF THE FIRM