

**SCHEDULE OF QUANTITIES**

**White washing & painting and repairing in NIPFP campus, New Delhi**

**NOTE: 1-**Contractors are requested to quote the rates after inspecting the site

**2-**Contractors are requested to quote the rates inclusive of all the taxes.

**3-**Contractors are requested to submit the original bills against the purchase of required painting material from the authorised dealer of asian paints,before release of the R.A bills,if work awarded to him.

**4-**Contractor are required to deposit 50% of painting material of approved brand (theoretical consumption of material based on area considered in the estimate) in NIPFP store before start of work at site .

| Item     | Description of Item   | Quantity | Unit  | Rate       | Amount     |
|----------|---|----------|-------|------------|------------|
|          |   |          |       | <b>Rs.</b> | <b>Rs.</b> |
| <b>1</b> | <b>PLASTIC EMULSION PAINT</b>   |          |       |            |            |
| Exist    | Providing and applying of two coat of pre approved Plastic acrylic emulsion paint (Apcolite asian/super cover ICI/easy clean Berger ) to walls and partition including scrappingand, sand parering ,surface preparation with one coat of putty ,primer and sanding all complete. with necessary drying period for each coat. The final finished should be a uniform and neet finish to the satisfaction of Institute for all hight and surface including cost of scaffolding etc required to reach double height in library nothing will be paid extra for carrying out the double height work. | 3350     | sq.m. |            |            |
| <b>2</b> | <b>SYNTHETIC EMULSION PAINT</b>   |          |       |            |            |

|                     |   |      |       |  |             |
|---------------------|---|------|-------|--|-------------|
| Ex.                 | Painting with synthtic emulsion paint of approved brand and manufactured of required colour two or more coats of suitable shed with ordinary paint of approved brand and manufacture to give an even shed . Make : Asian,(Apcolite,ICI Dulux. | 500  | sq.m. |  |             |
| 3                   | <b>POP PUNNING</b>  |      |       |  |             |
| DSR                 | Providing and applying Plaster of Parid (super fine qualitu)punning with minimum thichness of 3mm and finish with surface smooth in fine.   | 130  | sq.m. |  |             |
| 4                   | <b>TEXTURED INTERIOR PAINT</b>  |      |       |  |             |
|                     | Finishing wall with textured interior paint of required shed (a) Old work (one or more coats) applied @ 1.82 ltrs/10 sqm  | 25   | sq.m. |  |             |
| 5                   | <b>POLISHING ON WOOD WORK</b>   |      |       |  |             |
| DSR                 | Polishing on wooden work with ready made mixed wax polish on door,almirh ralling etc of approved brand and manufacture .  | 1400 | sq m. |  |             |
| 6                   | <b>MELAMINE POLISHING</b>   |      |       |  |             |
|                     | Melamine polishing on wooden work (one or more coats)   | 210  | sq.m. |  |             |
|                     |   |      |       |  |             |
|                     |   |      |       |  |             |
| <b>TOTAL AMOUNT</b> |   |      |       |  | <b>0.00</b> |
|                     |   |      |       |  |             |
|                     |   |      |       |  |             |

Signature of contractor